

QUOTATION.

No. **WI-10100**
Date **29 Sept 2026**
Valid until **14 Oct 2026**

PREPARED FOR

Shahzad Ahmed
0300 1234567

PROJECT

Renovation Work of Shahzad Sb House
112-A Ahmad Block, Lahore

SR. NO	PARTICULARS	ITEMS	AMOUNT (RS)
1	CIVIL WORK	5	682,000
2	FLOORING	9	1,618,875
3	CEILING	2	120,000
4	PAINT WORK	3	132,125
5	WOOD WORK	7	1,187,650
6	GLASS WORK	5	416,650
7	BATH FITTING, FIXTURES AND ACCESSORIES	5	-
8	CURTAIN AND BLINDS	4	65,250
9	ELECTRICAL WORK	1	-
10	PLUMBING WORK	1	-

TOTAL (Rs) **4,222,550**

Amount in words: **Rupees Forty Two Lakh Twenty Two Thousand Five Hundred Fifty Only**

Approved by

Consultant
Woodex Interior

Client
Shahzad Ahmed



5 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Removal of existing windows, marble, brick walls and slabs demolished wherever required	1	L/S	50,000	50,000
2	Removal and disposal of bath tiles	1	L/S	50,000	50,000
3	A class brick work, beam/girder and slab pouring 1:4:8, PCC and plaster as per drawing	256	sft	2,000	512,000
4	MS girder	2	L/S	35,000	70,000
5	Transportation	1	L/S	-	-
Total • Civil Work					682,000



02 FLOORING

9 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Floor tile, Master Bath (01), full body porcelain	17	sq m	3,200	54,400
2	Wall tile, Master Bath (01)	62	sq m	3,200	198,400
3	Floor tile, Bath (02)	12	sq m	3,200	38,400
4	Wall tile, Bath (02)	35	sq m	3,200	112,000
5	Cement, sand, tile bond and filling as directed by consultant	1,355	sft	65	88,075
6	Laying and fixing 2x4 porcelain tiles with mortar, joint filling and curing complete	1,355	sft	120	162,600
7	Laminate floor, Room 01 and 02	700	sft	1,350	945,000
8	Wooden skirting 4"	150	rft	-	-
9	Transportation	1	L/S	20,000	20,000
Total · Flooring					1,618,875



03 CEILING

2 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	POP false ceiling with aluminum channels and steel hanging wire, as per approved design	1,000	sft	120	120,000
2	Transportation	1	L/S	-	-
Total · Ceiling					120,000



3 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Ceiling paint, plastic emulsion 4 coats	1,000	sft	80	80,000
2	Wall paint, plastic emulsion 4 coats	695	sft	75	52,125
3	Transportation	1	L/S	-	-
Total • Paint Work					132,125



05 WOOD WORK

7 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Media wall, Master Bed 01, supply making and fixing	142.5	sft	1,200	171,000
2	Media wall, Bed 02	121.125	sft	1,200	145,350
3	Bed wall, Master Bed 01	142.5	sft	1,200	171,000
4	Bed wall, Bed 02	102.125	sft	1,200	122,550
5	Wardrobe, Master Bath 01	92.625	sft	2,800	259,350
6	Wardrobe, Bath 02	76	sft	2,800	212,800
7	Dressing cabinet, Master Bath 01	48	sft	2,200	105,600
Total · Wood Work					1,187,650



06 GLASS WORK

5 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Aluminium windows, Master Bed O1	128	sft	1,500	192,000
2	Aluminium windows, Bed O2	27.5	sft	1,500	41,250
3	12mm tempered glass, Master Bath O1	20	sft	1,800	36,000
4	12mm tempered glass, Bath O2	68	sft	1,800	122,400
5	Transportation	1	L/S	25,000	25,000
Total · Glass Work					416,650



07 BATH FITTING, FIXTURES AND ACCESSORIES

5 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Muslim shower with fittings	10	each	-	-
2	Vanity mixer tap	10	each	-	-
3	Floor mounted W.C with fittings	10	each	-	-
4	Vanity	10	each	-	-
5	Paper holder, floor trap and accessories	32	each	-	-
Total · Bath Fitting, Fixtures and Accessories					-



08 CURTAIN AND BLINDS

4 items

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Curtain, Master Bed 01, making providing and fixing	145	sft	450	65,250
2	Curtain, Bed 02	80	sft	-	-
3	Blackout blinds, Master Bed 01	145	sft	-	-
4	Blinds, Bed 02	80	sft	-	-
Total · Curtain and Blinds					65,250



09 ELECTRICAL WORK

1 item

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Complete electrical work, making providing and fixing	1	L/S	-	-
Total · Electrical Work					-



10 PLUMBING WORK

1 item

SR	PARTICULARS	TOTAL AREA / QTY	UNIT	RATE (RS)	AMOUNT (RS)
1	Water supply and drainage for 2 baths, providing laying and fixing	1	L/S	-	-
Total · Plumbing Work					-



TERMS & CONDITIONS

1. 50% advance payment with work order.
2. Payment will be charged on the actual dimension / size of area.
3. Rates are valid for 15 days as per market rates.

ACCEPTANCE

I accept this quotation (WI-10100, Rs 4,222,550) and the terms above.

Client signature

Shahzad Ahmed

Date

For Woodex Interior